BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/19/2017-18 Dated: 17-02-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 35

Name of Work:-Improvements to roads and drains at Harohalli village and surrounding areas in ward no-02 of yelahanka Sub Division,

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri M.N.RAMAIAH	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no141, PWD SR 2016-17)	Cum	218.40	91.25	Rupees Ninety One and Paise Twenty Five Only
2	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2016-17	Cum	250.70	314.92	Rupees Three Hundred Fourteen and Paise Ninety Two Only
3	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2016-17)	Cum	469.10	75.67	Rupees Seventy Five and Paise Sixty Seven Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri M.N.RAMAIAH	
				Rate	Rate in Words
4	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(Item no 4.3,Page no12,PWD SR 2016-17)	Cum	47.40	5415.94	Rupees Five Thousand Four Hundred Fifteen and Paise Ninety Four Only
5	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work (pwd sr2016-17,p.no13,sno4.11)	Cum	133.26	6688.97	Rupees Six Thousand Six Hundred Eighty Eight and Paise Ninety Seven Only
6	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe55 0(pwd sr2016-17,p.no17,s.no4.46)	Tonne	11.48	63096.19	Rupees Sixty Three Thousand Ninety Six and Paise Nineteen Only
7	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters, bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecificationS.Specification no.KBS 4.6.2 (pwd sr2016-17 p.no15/4.31)	Sqm	1010.00	326.05	Rupees Three Hundred Twenty Six and Paise Five Only
8	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	252.00	2204.58	Rupees Two Thousand Two Hundred Four and Paise Fifty Eight Only

M N Ramaiah,
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.